

FOURTH FLOOR DEMOLITION WORK PART PLAN

GENERAL DRAWING NOTES:

1. ITEMS SHOWN CROSS HATCHED TO BE REMOVED IN ITS ENTIRETY, INCLUDING ALL ASSOCIATED DUCTWORK, HANGERS, INSERTS, GUIDES, ETC. 2. DEMOLITION, RELOCATION, AND NEW WORK SHALL BE PHASED TO MINIMIZE DISRUPTION OF BUILDING FUNCTIONS. PROVIDE TEMPORARY CAPPING AND CONNECTIONS AS REQUIRED TO MAINTAIN EXISTING SYSTEMS DURING CONSTRUCTION. COORDINATE ALL SHUT-DOWNS WITH THE OWNER AND

CONSTRUCTION MANAGER. 3. COORDINATE DEMO OF BMS NETWORK WITH CONTROLS VENDOR.

4. GENERAL CONTRACTOR TO ENGAGE BALANCING CONTRACTOR TO PROVIDE PRE—CONSTRUCTION BALANCING REPORT TO INCLUDE ALL DIFFUERS AND VAV BOXES IN SCOPE, STATIC PRESSURE AND AIRFLOW READINGS AND DUCT MAIN TAKE—OFFS, AIR HANDLING UNIT AND EXHAUST FAN RPM, HP, S.P. AND AIRFLOW READINGS.

PROJECT NO:

jg Associates

ARCHITECTS PLANNERS INTERIOR DESIGN

8 SUMMIT ROAD, LEXINGTON MA. 02421 TEL-781-861-7812 FAX: 781-353-6006


CONSULTANTS

PROJECT:

OTOLARYNGOLOGY LAB FOURTH FLOOR-MEEI 243 CHARLES ST, BOSTON-MA

OWNER:





REVISIONS

DRAWN: MMR DATE: September 26, 2012

JOB NO:

SCALE : 1/8"=1'-0"

DRAWING NO. SHEET __ OF TOTAL __ SHEETS